



Coco Van
Airstream Kitchen
 Providenciales, T&C

Uni-Source Supply
 International Inc.
 2055 W 73rd Street, Miami, FL 33016
 Ph: (305)826-8696 Fax: (305)826-9131

EQUIPMENT SCHEDULE					
ItemNo	Category	Mfr	Model	Quantity	Equipment Remarks
1	FRYER	SOUTHBEND	SB35S	2	
2	COUNTERTOP GRIDDLE	STAR	636MF	1	
3	COUNTERTOP HOTPLATE	STAR	604HF	1	
4	CHARBROILER	STAR	6024CBF	1	
6	EQUIPMENT STAND	ADVANCE TABCO	ES-248	1	
14	ICE BIN	KROWNE	KR18-36	1	
	FINISHED BACK	RENOVASHIP	FINISH BACK	1	
16	WORK TABLE	ADVANCE TABCO	FMS-244	1	
16.1	SHELVING, WALL-MOUNTED	RENOVASHIP	WS-12-36	1	
17	SANDWICH / SALAD PREPARATION REFRIGERATOR	CONTINENTAL REFRIG	SW72-12	1	
19	CONVECTION OVEN	MVP GROUP	AX-413	1	
19.1	EQUIPMENT STAND	ADVANCE TABCO	ES-242	1	
20	WORKTOP FREEZER	CONTINENTAL REFRIG	SWF36-FB	1	
21	REFRIGERATED WORK TOP	CONTINENTAL REFRIG	SW36-FB	1	
25	REACH-IN REFRIGERATOR	TRUE	T-12G-LD	1	
27	TABLE WITH SINK	RENOVASHIP	REAR TABLE	2	
	HAND SINK	VOLLRATH	201250	2	
	FAUCET	KROWNE	16-301L	2	
	FAUCET	KROWNE	15-512L	2	
29	TABLE	RENOVASHIP	FRONT TABLE	1	
30	WALL SHELF	RENOVASHIP	SHELF	1	
31	WALL SHELF	RENOVASHIP	SHELF	2	
32	EXHASUT HOOD	CAPTIVE-AIRE	HOOD	1	
33	EXHAUST FAN	CAPTIVE-AIRE	FAN	1	
34	WHEEL WELL (Left & Right)	RENOVASHIP	WHEEL WELL	1	

REAR ELEVATION

EQUIPMENT LAYOUT

All Dimensions to be verified on the job site.
 Actual locations for floor drains, and any ventilating equipment to be determined by Engineer.
 Mechanical, Plumbing & Electrical to be checked and verified by Customers MEP Engineer.
 Remote Condensing Units to be located by Architect.
 Exhaust & Supply fans to be located by Architect.

No.	Revision/Issue	Date
3	Updated after comments from Stuart & Andy	3-17-16
4	Reviewed Sandwich Unit and Dosing	4-9-16
5	Added MEP Details	5-10-16
6	Adjusted Size of Trailer after measurements	6-17-16

Date
June 17, 2016
 Drawn By
Dayne Gauntlett
 Scale
1/2" = 1'0"

Sheet
AK-1