



**Parrot Cay  
Beach Bar**  
Parrot Cay, T&C

**Uni-Source Supply**  
International Inc.  
2055 W 73rd Street, Miami, FL 33016  
Ph: (305)826-8696 Fax: (305)826-9131

EQUIPMENT SCHEDULE					
ItemNo	Category	Mfr	Model	Quantity	Equipment Remarks
1	CORNER ANGLE FILLER	KROWNE	KR18-DRC90	2	
1.1	STORAGE CABINET	KROWNE	KR18-SD24	2	
2	COCKTAIL STATION	KROWNE	KR18-W48L-10	1	
3	BOTTLE DISPLAY	KROWNE	KR18-24RD-LC	1	
3.1	BOTTLE DISPLAY	KROWNE	KR18-18RD-LC	1	
4	UNDERBAR ADD-ON UNIT	KROWNE	KR18-T12	1	
5	DRAINBOARD	KROWNE	KR18-RS18	1	
6	ICE BIN	KROWNE	KR18-24	1	
7	BLENDER STATION	KROWNE	KR18-12BD	2	
8	GLASSWASHER	KROWNE	GWR-24	1	
9	HAND SINK	KROWNE	KR18-SD12C	1	
10B	BACK BAR COOLER	TRUE	TBB-24-60G-SD-S-LD	1	
11	BOTTLE COOLER	KROWNE	BC24-SS	1	
21	THREE (3) COMPARTMENT SINK	ADVANCE TABCO	FC-3-1818-18R	1	
21.1	WALL / SPLASH MOUNT FAUCET	KROWNE	14-812L	1	
23B	REACH-IN REFRIGERATOR	TRUE	T-23-HC	1	
24	WIRE SHELVING UNIT	NEXEL	24726N	2	
25B	ICE CUBER	KOLD-DRAFT	GB1064RC	1	
26B	REMOTE CONDENSER UNIT	KOLD-DRAFT	RC314APV	1	

No.	Revision/Issue	Date
1	Preliminary Layout	9-22-16
2	Updated based on comments	9-28-16
3	Updated optional items based on Order	10-07-16
4		

Date  
**Oct 07, 2016**  
Drawn By  
**Dayne Gauntlett**  
Scale  
**1/4" = 1'0"**

Sheet  
**BB-1**

## EQUIPMENT LAYOUT

All Dimensions to be verified on the job site.  
Actual locations for floor drains, and any ventilating equipment to be determined by Engineer.  
Mechanical, Plumbing & Electrical to be checked and verified by Customers MEP Engineer.  
Remote Condensing Units to be located by Architect.  
Exhaust & Supply fans to be located by Architect.